


CEILING SYSTEMS

[Between us, ideas become reality.]®

TECHZONE™
Ceiling Systems
Submittal Document

4' Module – 6'-6" On-Center Technical Zone Spacing

**24" x 24" Field Panels,
6" x 48" Technical Panels**



COMPONENTS:

PANEL	EF = 0.923
MAINS	EF = 0.25
4' CT	EF = 0.615
2' CT	EF = 0.231


NOTE: Multiply ceiling area (SF) by the Estimating Factors (EF) to determine lineal footage of grid components and square footage of ceiling panels required.

Check specified items

15/16" GRID			9/16" GRID		
DESCRIPTION	ITEM #	✓	DESCRIPTION	ITEM #	✓
Field Panels					
Optima 24" x 24" x 1" Sq. Lay-in	3152	<input type="checkbox"/>	Optima 24" x 24" x 1" Sq. Tegular	3251	<input type="checkbox"/>
Optima 24" x 24" x 1" Sq. Tegular	3250	<input type="checkbox"/>	Ultima 24" x 24" x 3/4" Bev. Tegular	1912	<input type="checkbox"/>
Ultima 24" x 24" x 3/4" Sq. Lay-in	1910	<input type="checkbox"/>			
Ultima 24" x 24" x 3/4" Bev. Tegular	1911	<input type="checkbox"/>			
Technical Panels					
Optima 6" x 48" x 1" Sq. Lay-in	1400	<input type="checkbox"/>	Optima 6" x 48" x 1" Sq. Lay-in	1401	<input type="checkbox"/>
Optima 6" x 48" x 1" Sq. Tegular	1402	<input type="checkbox"/>	Optima 6" x 48" x 1" Sq. Tegular	1403	<input type="checkbox"/>
Ultima 6" x 48" x 3/4" Sq. Lay-in	1420	<input type="checkbox"/>	Ultima 6" x 48" x 3/4" Sq. Lay-in	1420	<input type="checkbox"/>
Ultima 6" x 48" x 3/4" Bev. Tegular	1422	<input type="checkbox"/>	Ultima 6" x 48" x 3/4" Bev. Tegular	1423	<input type="checkbox"/>
Metal 6" x 48" x .025" Sq. Lay-in	1650	<input type="checkbox"/>	Metal 6" x 48" x .025" Sq. Lay-in	1652	<input type="checkbox"/>
Metal 6" x 48" x .025" Sq. Tegular	1654	<input type="checkbox"/>	Metal 6" x 48" x .025" Sq. Tegular	1656	<input type="checkbox"/>
Grid Components					
Prelude 12' ID/HD Main Beam	7300/7301*	<input type="checkbox"/>	Suprafine 12' ID/HD Main Beam	7500/7501*	<input type="checkbox"/>
Prelude 4' Cross-Tee	XL7340/7341**	<input type="checkbox"/>	Suprafine 4' Cross-Tee	XL7540/7541**	<input type="checkbox"/>
	XL7342/7348**	<input type="checkbox"/>	Suprafine 2' Cross-Tee	XL7520	<input type="checkbox"/>
Prelude 2' Cross-Tee	XL7328	<input type="checkbox"/>	Interlude 12' ID Main Beam	6100	<input type="checkbox"/>
			Interlude 4' Cross-Tee	XL6140	<input type="checkbox"/>
			Interlude 2' Cross-Tee	XL6120	<input type="checkbox"/>

* main beam selected based on code/load requirement
** cross tee selected based on code/load requirement

**24" x 72" Field Panels,
6" x 48" Technical Panels**



COMPONENTS:

PANEL	EF = 0.923
MAINS	EF = 0.25
6' CT	EF = 0.231
4' CT	EF = 0.308

NOTE: Multiply ceiling area (SF) by the Estimating Factors (EF) to determine lineal footage of grid components and square footage of ceiling panels required.

Check specified items

15/16" GRID			9/16" GRID		
DESCRIPTION	ITEM #	✓	DESCRIPTION	ITEM #	✓
Field Panels					
Optima 24" x 72" x 3/4" Sq. Lay-in	3161	<input type="checkbox"/>	Optima 24" x 24" x 1" Sq. Tegular	3251	<input type="checkbox"/>
Optima 24" x 72" x 1" Sq. Tegular	3281	<input type="checkbox"/>	Optima 24" x 72" x 1" Sq. Tegular	3261	<input type="checkbox"/>
Technical Panels					
Optima 6" x 48" x 1" Sq. Lay-in	1400	<input type="checkbox"/>	Optima 6" x 48" x 1" Sq. Lay-in	1401	<input type="checkbox"/>
Optima 6" x 48" x 1" Sq. Tegular	1402	<input type="checkbox"/>	Optima 6" x 48" x 1" Sq. Tegular	1403	<input type="checkbox"/>
Metal 6" x 48" x .025" Sq. Lay-in	1650	<input type="checkbox"/>	Metal 6" x 48" x .025" Sq. Lay-in	1652	<input type="checkbox"/>
Metal 6" x 48" x .025" Sq. Tegular	1654	<input type="checkbox"/>	Metal 6" x 48" x .025" Sq. Tegular	1656	<input type="checkbox"/>
Grid Components					
Prelude 12' ID/HD Main Beam	7300/7301*	<input type="checkbox"/>	Suprafine 12' ID/HD Main Beam	7500/7501*	<input type="checkbox"/>
Prelude 6' Cross-Tee	XL7390	<input type="checkbox"/>	Suprafine 6' Cross-Tee	XL7590	<input type="checkbox"/>
Prelude 4' Cross-Tee	XL7340/7341**	<input type="checkbox"/>	Suprafine 4' Cross-Tee	XL7540/7541**	<input type="checkbox"/>
	XL7342/7348**	<input type="checkbox"/>	Interlude 12' ID Main Beam	6100	<input type="checkbox"/>
			Interlude 6' Cross-Tee	XL6190	<input type="checkbox"/>
			Interlude 4' Cross-Tee	XL6140	<input type="checkbox"/>

* main beam selected based on code/load requirement
** cross tee selected based on code/load requirement

To order TechZone ceiling systems samples:

- Contact your distributor
- Call 1 877 ARMSTRONG (276-7876)
- Log on to armstrong.com/contractoronly and select samples from the Bid list

